

Project Overview:

Name:	SOLITON_FTTB_2023/2024_GTD149075-HELEN PLAZA
Description:	
Project leader:	SOLITON TELMEC LTD
Customer:	SAFARICOM PLC
Status:	In Progress
Start:	9/21/2023 2:41:24 PM
Finish:	9/28/2023 2:41:24 PM

Item Description	Costs
Service Costs	Ksh 128,742.92
Material costs	Ksh 25,792.00
Total Excluding VAT	Ksh 154,534.92

Report Created By

cowuor

Christine Owuor

SOLITON_FTTB_2023/2024_GTD149075-HELEN PLAZA



Section A Service Costs

Item Description	Price / m	QTY	Total			
Linearised Rate for Fiber Deployment						
GF-Planning Services(1.2/0.6 Trench)	23.23	2	46.46			
GF-Project Management Incl of H&S (1.2/0.6 Trench)	59.63	2	119.26			
GF-Civil Works for Main Route(1.2 Trench)		556.82	2	1,113.64		
Total Linearised Rate :				Ksh 1,279.36		
Item Description	UOM	Price	QTY	Total		
Installation of Aerial Cable	m	43.00	280	12,040.00		
Installation of ATB	pce	528.00	1	528.00		
Supply, Install PlasticTrunking size 38*25mm	m	90.00	20	1,800.00		
As built documents	m	5.28	177	934.56		
Field detailed survey report	m	16.00	177	2,832.00		
Project Management Aerial Incl of H&S per meter	m	47.00	177	8,319.00		
Pole Down-lead clamp, Supply and Installation	pce	1,500.00	2	3,000.00		
Pole Cable Bracket, Supply and Installation	pce	2,200.00	2	4,400.00		
Pole, Supply & installation Wooden 8m	pce	11,000.00	2	22,000.00		
Pole Tangent Support, Supply and Installation	pce	1,800.00	3	5,400.00		
Supply and installation of Universal Pole bracket	pce	1,250.00	5	6,250.00		
Pole Tension Clamp, Supply and Installation	pce	2,300.00	10	23,000.00		
ISP Building As built documents per building	pce	880.00	1	880.00		
ISP Building Survey, Design per building	pce	4,400.00	1	4,400.00		
ISP Building Acquisition	pce	30,800.00	1	30,800.00		
Splicing, Testing and Commissioning 1 Core	pce	440.00	2	880.00		
Total Brown Field :				Ksh 127,463.56		

Report Created By

cowuor

Christine Owuor



Section B Material costs

Item Description	UOM	Price	QTY	Total
2 core Access terminal box (ATB)	Piece	420.00	1	420.00
HDPE Low Friction, Silicon lined 32/26mm-New	meter	83.84	10	838.40
ADSS fiber cable, 100m s/s clear span 12xSM G652D	meter	87.62	280	24,533.60
Total Material costs :				Ksh 25,792.00

Report Created By

cowuor

Christine Owuor



APPROVAL:

Title	Name	Signature	Date
Planner (Contractor)			
Project Manager (Contractor)			
Safaricom Plc Engineer			
Safaricom Plc Manager			
Safaricom Plc Sn. Manager			

Created: Monday, September 25, 2023